

CONTENTS

1. INTRODUCTION	7
2. TWO CONCEPTS OF STEAM GENERATORS FOR FAST REACTORS COOLED BY LIQUID SODIUM	9
2.1. Steam generators with sodium at the shell side	9
2.2. Steam generators with sodium flow inside the tubes	9
3. DESIGN CONCEPT OF THE MICROMODULE INVERSE STEAM GENERATOR (MMISG)	19
3.1. The lay-out of the MMISG	19
3.2. Design of the MMISG branches and modules	25
3.3. Supporting framework	28
3.4. Leak monitoring system	29
3.4.1. Double tube plate leak detection system	29
3.4.2. Water/steam leak into sodium monitoring and surveillance system . .	30
3.4.3. Monitoring of sodium leaks into the MMISG box	30
3.5. Choice of structural materials	31
3.6. Media quality requirements	32
3.7. Hydraulic characteristics of the MMISG	34
3.8. Stress analysis	36
3.8.1. Allowable stresses	36
3.8.2. Stress analysis of the tube plate	37
3.9. Heat transfer calculations	40
4. DESIGN CONCEPT OF THE MODULAR INVERSE STEAM GENERATOR (MISG)	44
4.1. The lay-out of the MISG	44
4.2. Design of the inverse steam generator module	49
4.3. Supporting framework	55
4.4. Leak monitoring system	55
4.5. Choice of structural materials	55
4.6. Media quality requirements	55
4.7. Hydraulic characteristics of the MISG	57
4.8. Stress analysis	59
4.8.1. Remarks on the stress analysis	59
4.8.2. Vibrating stability of the tube bundle	61
4.9. Heat transfer calculations	62
5. COMPARISON OF THE DESIGN CHARACTERISTICS OF THE MMISG AND MISG	65
6. OPERATIONAL CHARACTERISTICS OF THE MMISG ACHIEVED AT THE BOR 60 REACTOR	67
6.1. Parameters at the MMISG steady state power level	67
6.2. Overall heat transfer in the first period of the MMISG operation	67
6.3. Water and sodium flow and temperature distribution in branches	69

6.4. Hydraulic instability	71
6.5. Heating of the MMISG	72
6.6. Properties of structural materials after 27 000 hours of operation	73
7. OPERATIONAL CHARACTERISTICS OF THE MISG ACHIEVED AT THE BOR 60 REACTOR	75
7.1. Parameters at the MISG steady state power level	75
7.2. Heat transfer	76
7.2.1. Heat transfer research on a steam generator model	76
7.2.2. Methodical viewpoints of the heat transfer assessment	76
7.2.3. Results of the heat transfer assessment	79
7.3. Distribution of sodium temperature at the tube bundle	88
7.4. Heating of the MISG	91
8. COMPARISON OF OPERATIONAL CHARACTERISTICS OF THE MMISG AND MISG AND SUMMARY OF THE EXPERIENCE GAINED	92
9. SUMMARY AND ANALYSIS OF RESULTS OF THE STUDY	99
10. CONCLUSIONS AND RECOMMENDATIONS	102
REFERENCES	105
CONTRIBUTORS TO DRAFTING AND REVIEW	109